8. List of approximate quantity of shed materials for the use of North and South Banks of the Krishnarajasagara Works.

No.	Particulars	Unit	Quantity required for	
			North Bank	South Bank
1	Big bamboo, 11′ to 13′ long	100	2,500	10,000
2	Thin bamboo, 11′ to 12′ long	100	1,800	6,000
3	Nowgany bamboo, 11′ to 18′ long	100	..	..
4	Cocoa leaves, 2½′ x 1½′	100	6,000	50,000
5	Bamboo mats, 6′ x 5½′	Each	100	200
6	Thalachery coir ropes of 65 pieces	Bundle	30	200
7	Bamboo bailing basket	Each	200	..
8	Casuarina poles 24′ and girth 1½′	Do	500	..
9	Kalavadi rope of 100 pieces	Bundle	200	..

N. KRISHNIENGAR,
For *Executive Engineer, Dam Construction Dn.*

MISCELLANEOUS DEPARTMENTS.

GOVERNMENT OF MYSORE ELECTRICAL DEPARTMENT.

Dated 26th February 1923.

Notice is hereby given that sealed tenders will be received at the Office of the Chief Electrical Engineer to the Government of Mysore, up to 12 noon of Thursday the 29th March 1923, for constructing a compound wall around the Bangalore Power and Lighting Stores and Workshop, Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1923.

2. The plans, detailed estimate and conditions may be seen at the Chief Electrical Engineer's Office at Bangalore between the hours of 11 A.M. and 4 P.M. on working days.

3. Tenders should be submitted on printed forms, which may be obtained from the Chief Electrical Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items of work specified, will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "tenders for constructing a compound wall around the Bangalore Power and Lighting Stores and Workshop, Bangalore," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Electrical Engineer to the Government of Mysore, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Chief Electrical Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract of detailed quantities for constructing a compound wall around the Bangalore Power and Lighting Stores and Workshop, Bangalore.

No.	Items of work	Per	Quantity
1	Earthwork excavation	C. yd.	96
2	Stone in clay, foundation and basement with bond stones 6′ apart	C. ft.	3,472
3	Burnt brick in clay, superstructure	,,	4,751
4	Burnt brick in mortar, superstructure	,,	162
5	Chunam plastering	Sqr.	127·39
6	Chunam pointing	,,	22·88
7	White and colourwashing	,,	150·27
8	Brick in mortar, coping with glass pieces on top	R. ft.	1,118
9	Cornice and capitals on top of gate pillars	Each	4
10	Iron gates 12′ x 6½′	,,	2
11	Iron wicket gates	,,	3
12	Bond stones (2′ x 2′ x ½′)	,,	12
13	Chunam putty over roof	R. ft.	6
14	Honey-wood work with wood oiling	C. ft.	1·35
15	Roofing with Mangalore tiles on teak reepers 2″ x 1″	Sqr.	0·39
16	Plain cornice 6″ projection	R. ft.	18
17	Flooring with Cuddappa slabs on 3″ concrete 2nd cement pointed	Sqr.	0·25

B. D. NATH,
For *Chief Electrical Engineer, Government of Mysore.*